

# ***Forward Tracking Hodoscope***

***M. Khandaker***  
***SANE Readiness Meeting***  
***October 26, 2007***

# Tracking Hodoscope Design

## Location and Size:


- **Located 50 cm downstream of target directly in front of gas Čerenkov.**
- **Active area: 38 cm (vertical) × 21 cm (horizontal).**
- **128 bars along vertical and 72 along horizontal.**
- **Two Y planes, offset by 1.5 mm for redundancy, and one X plane.**

## Material:

- **Bicron BC-408 Plastic Scintillator (3 mm × 3 mm square).**
- **Bicron BCF-92MC multi-clad blue-green WLS Fiber (1.2 mm  $\varnothing$ , 2.5 m long).**
- **Fiber glued on to scintillator surface along length of bar.**
- **Scintillator/Fiber unit wrapped with Teflon for reflectivity.**

# Tracker Readout System

- **Single-ended readout with multianode PMT.**
- **Preamplifier, Discriminator, and TDC per channel.**



- **Hodoscope not included in event trigger.**
- **Offset Y-planes' coincidence (in software) for reliability.**

## **Tracker Mount Support Frame**

- **Individual counter module stacked next to each other in each plane.**
- **Tedlar separator between counters to prevent light crosstalk.**
- **Counters held in place between two G-10 frames per plane.**
- **WLS fibers coupled to PMT with Delrin block adapter and optical grease.**
- **All three planes mounted to Čerenkov's front support frame.**
- **Shielded box with PMTs mounted on to Čerenkov's back support frame > 2 m away from target magnetic field.**

# Tracker Hardware and Electronics

<u>Item</u>	<u>Status</u>
● <b>Hamamatsu H8804 64-channel PMT</b>	<b>all units acquired</b>
● <b>BC-408 scintillators</b>	<b>all units acquired</b>
● <b>Multi-clad WLS fibers</b>	<b>all units acquired</b>
● <b>Fiber-PMT Mounting Adapter</b>	<b>all units acquired</b>
● <b>64-channel PMT signal cables</b>	<b>all units acquired</b>
● <b>Phillips 776 Preamplifier</b>	<b>Hall C (all chnls)</b>
● <b>LeCroy 4413 16-chnl Discriminators</b>	<b>LEGS/BNL (all chnls)</b>
● <b>LeCroy 1877 96-chnl Multihit TDCs</b>	<b>Hall C (all chnls)</b>
● <b>CAMAC Crate</b>	<b>LEGS/BNL (2)</b>
● <b>Ribbon Cables from Discr. to TDC</b>	<b>all units acquired</b>

# Tracker Construction Status


## Scintillator/Fiber Module:

- *All scintillator/fiber modules for both Y planes completed.*
- *30/72 modules for the X plane completed.*
- *One full Y plane of 128 bars mounted on support frame and completely instrumented.*

## Support Frame:

- *All three G-10 support frames constructed.*
- *Metal stand for one Y plane constructed.*

# Tracker Y Plane Tests



- **One Y plane of 128 bars in the hall for beam tests.**
- **Currently, mounted under the BigCal for tests with cosmics.**
- **Dedicated time available November 2-4, 2007.**

## **Tasks to be Completed**

- ***Complete rest of X-plane scintillator/fiber modules.***
- ***Complete mounting of modules in their support frames.***
- ***Work with Hall C designers for PMT shielding box, and mounting on to gas Čerenkov support structure.***